

Estimate Weight Summary Report

Lengths in Imperial

001007 El Greco-Tilt up

Weights in Imperial (lb)

Bid/Pages Included:

001 LUMP SUM WHOLE JOB

Takeoff In-Process Base Bid

----- Rebar-Black Weight by Grade -----

Size	Grade	A615	75 Grade	Grade A615	A706	Grade A36	Grade A82	Grade	ard Metric	ard Metric	Total
3/10 Bar	0	0	0	38716	0	0	0	0	0	0	38716
4/13 Bar	0	0	0	112738	0	0	0	0	0	0	112738
5/16 Bar	0	0	0	21844	0	0	0	0	0	0	21844
6/19 Bar	0	0	0	307965	0	0	0	0	0	0	307965
7/22 Bar	0	0	0	12520	0	0	0	0	0	0	12520
8/25 Bar	0	0	0	2998	0	0	0	0	0	0	2998
9/29 Bar	0	0	0	11956	0	0	0	0	0	0	11956
Total:	0	0	0	508736	0	0	0	0	0	0	508736

----- Rebar-Black Weight by Fab Type -----

Size	Stock	Straight	Spiral	Heavy	Medium	Light	Processed	Processed	Total
3/10 Bar	0	22029	0	0	0	16687	0	0	38716
4/13 Bar	0	108424	0	4313	0	0	0	0	112738
5/16 Bar	0	21292	0	339	0	213	0	0	21844
6/19 Bar	0	295513	0	7863	0	4589	0	0	307965
7/22 Bar	0	12520	0	0	0	0	0	0	12520
8/25 Bar	0	1175	0	1823	0	0	0	0	2998
9/29 Bar	0	11956	0	0	0	0	0	0	11956
Total:	0	472909	0	14338	0	21488	0	0	508736

----- FIELD INSTALLED -----

Sac	Part	Weight	Lb/Ft	Pieces	Ft/Piece	Lb/Piece	Straight	Heavy	Light
203	FOOTINGS, COLUMN PADS								
	5	213		24	8.5		0	0	213
	6	5500		526	7.0		5500	0	0
	7	6486		224	14.2		6486	0	0
	SAC Total:	12199	1.733	774	9.1	15.8	11986	0	213
214	FOOTINGS, MISC.								
	3	342		102	8.9		0	0	342
	4	616		89	10.4		554	61	0
	5	9976		70	136.6		9637	339	0
	6	2911		364	5.3		613	2298	0
	SAC Total:	13845	1.038	625	21.3	22.2	10805	2698	342
402	T/U PANELS (ALL)								
	3	16345		4978	8.7		0	0	16345
	4	7211		1882	5.7		2959	4252	0
	5	11654		284	39.3		11654	0	0
	6	299554		4707	42.4		289400	5565	4589
	7	6034		72	41.0		6034	0	0
	8	2998		34	33.0		1175	1823	0
	9	11956		74	47.5		11956	0	0
	SAC Total:	355752	1.306	12031	22.6	29.6	323178	11640	20933
602	REBAR SLAB, SOG								
	3	11160		280	106.0		11160	0	0
	4	104911		454	345.9		104911	0	0
	SAC Total:	116070	0.622	734	254.4	158.1	116070	0	0
677	SITWORK, PAVING								
	3	10869		66	438.0		10869	0	0
	SAC Total:	10869	0.376	66	438.0	164.7	10869	0	0

=====

INSTALLED TOTALS:	508736	1.001	14230	35.7	35.8	472909	14338	21488
-------------------	--------	-------	-------	------	------	--------	-------	-------

----- FOB ITEMS -----

Estimate Weight Summary Report

Lengths in Imperial

Weights in Imperial (lb)

001007 El Greco-Tilt up

Bid/Pages Included:

001 LUMP SUM WHOLE JOB

Takeoff In-Process Base Bid

Sac	Part	Weight	Lb/Ft	Pieces	Ft/Piece	Lb/Piece	Straight	Heavy	Light
	SAC Total:	0	0.000	0	0.0	0.0	0	0	0
		=====	=====	=====	=====	=====			
FOB TOTALS:		0	0.000	0	0.0	0.0	0	0	0