



Western Industries, Inc
 26828 Maple Valley Hwy # 247
 Maple Valley, WA. 98022
 (253) 326-5574-Phone
 (253) 326-5582-Fax

Contractor's License# (WESTERC891KC)
 DBE Certification# (D2M1021587)

CUST: SB Structures, LLC		Page 1 of 5
JOB: Shore Rd to Kitchen Rd		Order#: 00510-10
DESC: RETAINING WALL 3	Dwg #: 501	Made By: DM

BARLIST SUMMARY BY BEND TYPE

Item	Qty	Size	Length	Mark	Bend	Weight	A	B	C	D	E	F	G	H	K	R	J	O
1	316	4/13	3-5	E	2	721	0-8	2-9										
2	1	4/13	6-6	K4y	21	4			5-10	0-8				0-8	0-1			
3	93	4/13	6-6	K5	21	404			5-10	0-8				0-8	0-1			
4	1	4/13	6-7	K4x	21	4			5-11	0-8				0-8	0-1			
5	1	4/13	6-8	K4w	21	4			6-0	0-8				0-8	0-1			
6	1	4/13	6-9¼	K4v	21	5			6-1¼	0-8				0-8	0-1			
7	1	4/13	6-10¼	K4u	21	5			6-2¼	0-8				0-8	0-1			
8	1	4/13	6-11¼	K4t	21	5			6-3¼	0-8				0-8	0-1			
9	1	4/13	7-0½	K4s	21	5			6-4½	0-8				0-8	0-1			
10	1	4/13	7-1½	K4r	21	5			6-5½	0-8				0-8	0-1			
11	1	4/13	7-2½	K4q	21	5			6-6½	0-8				0-8	0-1			
12	1	4/13	7-3¾	K4p	21	5			6-7¾	0-8				0-8	0-1			
13	1	4/13	7-4¾	K4o	21	5			6-8¾	0-8				0-8	0-1			
14	1	4/13	7-5¾	K4n	21	5			6-9¾	0-8				0-8	0-1			
15	1	4/13	7-7	K4m	21	5			6-11	0-8				0-8	0-1			
16	1	4/13	7-8	K4l	21	5			7-0	0-8				0-8	0-1			
17	1	4/13	7-9	K4k	21	5			7-1	0-8				0-8	0-1			
18	1	4/13	7-10¼	K4j	21	5			7-2¼	0-8				0-8	0-1			
19	1	4/13	7-11¼	K4i	21	5			7-3¼	0-8				0-8	0-1			
20	1	4/13	8-0¼	K4h	21	5			7-4¼	0-8				0-8	0-1			
21	1	4/13	8-1½	K4g	21	5			7-5½	0-8				0-8	0-1			
22	1	4/13	8-2½	K4f	21	5			7-6½	0-8				0-8	0-1			
23	1	4/13	8-3	K2y	21	6			7-7	0-8				0-8	0-1			
24	1	4/13	8-3½	K4e	21	6			7-7½	0-8				0-8	0-1			
25	1	4/13	8-4	K2x	21	6			7-8	0-8				0-8	0-1			
26	1	4/13	8-4¾	K4d	21	6			7-8¾	0-8				0-8	0-1			
27	1	4/13	8-5	K2w	21	6			7-9	0-8				0-8	0-1			
28	1	4/13	8-5¾	K4c	21	6			7-9¾	0-8				0-8	0-1			
29	1	4/13	8-6	K2v	21	6			7-10	0-8				0-8	0-1			
30	74	4/13	8-6	K3	21	420			7-10	0-8				0-8	0-1			
31	1	4/13	8-6¾	K4b	21	6			7-10¾	0-8				0-8	0-1			



Western Industries, Inc
 26828 Maple Valley Hwy # 247
 Maple Valley, WA. 98022
 (253) 326-5574-Phone
 (253) 326-5582-Fax

Contractor's License# (WESTERC891KC)
 DBE Certification# (D2M1021587)

CUST: SB Structures, LLC		Page 4 of 5
JOB: Shore Rd to Kitchen Rd		Order#: 00510-10
DESC: RETAINING WALL 3	Dwg #: 501	Made By: DM

BARLIST SUMMARY BY BEND TYPE

Item	Qty	Size	Length	Mark	Bend	Weight	A	B	C	D	E	F	G	H	K	R	J	O
94	1	4/13	8-7	G2c		6												
95	1	4/13	8-9	G2b		6												
96	136	4/13	8-10	G		802												
97	1	4/13	8-10	G2a		6												
98	10	4/13	12-8	Q4		85												
99	10	4/13	14-0	Q3		94												
100	10	4/13	17-10	Q2		119												
101	4	4/13	24-0	L1		64												
102	10	4/13	24-9	Q1		165												
103	140	4/13	30-0	Q		2805												
104	110	4/13	47-8	L		3502												
	2217		SubTot			15470												

Total Bar Weight: 15470 Lbs.
Longest Length: 47-8

Total Weight: 15470 Lbs.

